

## Exhibit F

Construction ICRA:

Project number:

Area:

Date:

### Parkland Health INFECTION PREVENTION

#### CONSTRUCTION ACTIVITY TYPES

<b>TYPE A</b>	Inspection and non-invasive activities. Includes, but is not limited to: removal of ceiling tiles for visual inspection or replacement, painting (not sanding), wall covering, electrical trim work, installation of telephone and computer cables, minor plumbing, and activities that do not generate dust or require cutting of walls or access to ceilings other than for visual inspection or minor cable work.
<b>TYPE B</b>	Small scale, short duration activities that create minimal dust. Includes, but is not limited to, access to chase spaces or cutting of walls or ceiling where dust migration can be controlled.
<b>TYPE C</b>	Any work that generates a moderate to high level of dust or requires demolition or removal of any fixed building components or assemblies. Includes, but is not limited to sanding walls for painting or wall coverings; removing floor coverings, ceiling tiles and casework; new wall construction; minor ductwork or electrical work above ceilings; major cabling activities; and/or any activity that cannot be completed within a single work shift.
<b>TYPE D</b>	Major demolition and construction projects. Includes, but is not limited to activities that require consecutive work shifts, heavy demolition or removal of a complete ceiling system and new construction.

#### INFECTION PREVENTION RISK GROUPS

<b>Group 1 Low Risk</b>	<b>GROUP 2 Medium Risk</b>	<b>GROUP 3 High Risk</b>	<b>GROUP 4 Highest Risk</b>
1. Office Areas 2. Outside (not in areas commonly occupied by patients or staff) 3. Mechanical or IT closets	4. All other patient care units (e.g., ultrasound, cardiac rehab, other rehabilitation, PVI, neurophysiology) 5. Cafeteria 6. Engineering 7. Environmental services 8. Non-procedural outpatient clinics	1. Emergency Room 2. Radiology/MRI 3. Post-anesthesia Care Units (PACUs) 4. Labor & Delivery 5. Newborn nurseries 6. Renal patients 7. Day Surgery 8. PT – tank areas 9. Outpatient surgery 10. Nuclear medicine 11. Admission/discharge units 12. Echocardiography 13. Medicine & WISH Inpatient Units 14. Laboratories 15. Blood draw area 16. Central sterile supply 17. Cardiopulmonary 18. Procedural Outpatient services	1. Surgery, inpatient 2. Labor & delivery operating rooms 3. Operating Rooms 4. Sterile Processing 5. Transplant 6. Cardiology 7. Cardiac catheterization & angiography areas 8. Dialysis unit or clinic 9. Intensive Care Units 10. Oncology unit or clinic 11. Anesthesia and pump areas 12. Endoscopy 13. Pharmacy admixture 14. Radiation therapy 15. Burn center

#### CONSTRUCTION ACTIVITY/INFECTION PREVENTION MATRIX

Infection Prevention consultation is required when the construction activity and risk level indicate that Class III and Class IV control procedures are necessary

<b>RISK LEVEL</b>	<b>CONSTRUCTION ACTIVITY</b>			
	<b>TYPE “A”</b>	<b>TYPE “B”</b>	<b>TYPE “C”</b>	<b>TYPE “D”</b>
<b>Group 1</b>	<b>I</b>	<b>II</b>	<b>II</b>	<b>III/IV</b>
<b>Group 2</b>	<b>I</b>	<b>II</b>	<b>III</b>	<b>IV</b>
<b>Group 3</b>	<b>I</b>	<b>II</b>	<b>III/IV</b>	<b>IV</b>
<b>Group 4</b>	<b>II</b>	<b>III/IV</b>	<b>III/IV</b>	<b>IV</b>

Construction ICRA:

Project number:

Area:

Date:

**INFECTION PREVENTION CONSTRUCTION RISK ASSESSMENT**

Location of Construction:			Project Start Date:		
Project Coordinator:			Estimated Duration:		
Contractor Performing Work:			Permit Expiration Date:		
Supervisor:			Telephone:		
YES	NO	CONSTRUCTION ACTIVITY	YES	NO	INFECTION CONTROL RISK GROUP
		TYPE A: Inspection and Non-Invasive activities			GROUP 1: Low Risk
		TYPE B: Small scale, short duration, minimal amount of dust generation			GROUP 2: Medium Risk
		TYPE C: Activity generates moderate to high levels of dust, requires greater than 1 work shift for completion			GROUP 3: High Risk
		TYPE D: Major demolition, construction, and duration. Requiring consecutive work shifts			GROUP 4: Highest Risk
CLASS I		1. Execute work by methods to minimize raising dust from construction operations. 2. Immediately replace any ceiling tile displaced for visual inspection. 3. Minor Demolition for Remodeling			
CLASS II		1. Provide active means to prevent airborne dust from dispersing. 2. Water mist work surfaces to control dust while cutting. 3. Seal unused doors with duct tape. 4. Wipe surfaces with IC approved disinfectant upon completion of work. 5. Contain construction waste before transport. 6. Wet mop and/or vacuum before leaving work area. 7. Place dust mat at entrance and exit of work area. 8. Isolate HVAC system in areas where work is being performed.			
CLASS III		1. Isolate HVAC system in areas where work is being performed. 2. Complete all critical barriers or implement containment units before construction begins. 3. Maintain excess exhaust over supply air during construction activities. 4. Maintain negative air pressure within work site utilizing HEPA equipped air filtration units. 5. Do not remove barriers from work area until complete project is thoroughly cleaned by Env. Services Dept. 6. Remove barrier materials carefully to minimize spreading of dirt and debris associated with construction. 7. Contain construction waste before transport in covered containers. 8. Cover transport receptacles or carts during transportation to and from site.			
Class IV		1. Isolate HVAC system in area where work is being performed. 2. Complete all critical barriers or implement containment unit method before construction begins. 3. Maintain excess exhaust over supply air during construction activities. 4. Maintain negative air pressure within work site utilizing HEPA equipped air filtration units. 5. Seal holes, pipes, conduits, and punctures appropriately. 6. Do not remove barriers from work area until completed project is thoroughly cleaned by the Environmental Service Dept. 7. Vacuum or wet mop work area. 8. Remove barrier materials carefully to minimize spreading of dirt and debris associated with construction. 9. Contain construction waste before transport in covered containers. 10. Cover transport receptacles or carts during transportation to and from site.			
<b>Additional Requirements:</b>					
Date Initials 12 Hour uninterrupted exchange required			Exceptions/Additions to this permit are noted by attached memoranda		
Unit Manager:			Date:		
Permit Request By:			Date:		
Permit Authorized By:			Date:		

Revised, Approved IPCC 03/13