

PROJECT SPECIFICATIONS

**El Monte City School District
Potrero Elementary School
Playground Equipment Replacement Project**

2611 Potrero Avenue
El Monte, California 91733

Prepared by:

**Bureau Veritas North America, Inc.
220 Technology Drive, Suite 100
Irvine, CA 92618**

Plan Check Submittal

May 5, 2026




TABLE OF CONTENTS

DIVISION 02 – EXISTING CONDITIONS

02 4119	Selective Demolition	3
---------	----------------------------	---

DIVISION 31 – EARTHWORK

31 1000	Site Clearing.....	9
31 2316	Excavating, Back-Filling and Compacting for Paving.....	14
31 2326	Base Course	19

DIVISION 32 – EXTERIOR IMPROVEMENTS

32 0113	Rolled Slurry Seal Existing Pavement.....	21
32 0117	Asphalt Pavement Repair	23
32 1723	Pavement Markings	27
32 1819	Solar Reflective Pavement Coating	29

END OF TABLE OF CONTENTS

SECTION 02 4119

SELECTIVE DEMOLITION

PART 1 - GENERAL

1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.02 SUMMARY

- A. Section Includes:

- 1. Demolition and removal of selected site elements.

- B. Related Requirements:

- 1. Division 01 for restrictions on the use of the premises, Owner-occupancy requirements, phasing requirements, temporary protection of existing trees and plants that are affected by selective demolition, and cutting and patching procedures.

1.03 DEFINITIONS

- A. Remove: Detach items from existing construction and legally dispose of them off-site unless indicated to be removed and salvaged or removed and reinstalled.
- B. Remove and Salvage: Carefully detach from existing construction, in a manner to prevent damage, and deliver to State.
- C. Remove and Reinstall: Detach items from existing construction, prepare for reuse, and reinstall where indicated.
- D. Existing to Remain: Existing items of construction that are not to be permanently removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.04 MATERIALS OWNERSHIP

- A. Unless otherwise indicated, demolition waste becomes property of Contractor.

1.05 PREINSTALLATION MEETINGS

- A. Predemolition Conference: Conduct conference at Project site.

1. Inspect and discuss condition of construction to be selectively demolished.
2. Review structural load limitations of existing structure.
3. Review and finalize selective demolition schedule and verify availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays.
4. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.
5. Review areas where existing construction is to remain and requires protection.

1.06 INFORMATIONAL SUBMITTALS

- A. Proposed Protection Measures: Submit report, including drawings, that indicates the measures proposed for protecting individuals and property, for environmental protection, for dust control, and for noise control. Indicate proposed locations and construction of barriers.
- B. Schedule of Selective Demolition Activities: Indicate the following:
 1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure Owner's on-site operations are uninterrupted
 2. Interruption of utility services. Indicate how long utility services will be interrupted.
 3. Coordination for shutoff, capping, and continuation of utility services.
 4. Use of elevator and stairs.
 5. Coordination of Owner's continuing occupancy of portions of existing building and of Owner's partial occupancy of completed Work.
- C. Inventory: Submit a list of items to be removed and salvaged and deliver to Owner prior to start of demolition.
- D. Predemolition Photographs: Submit before Work begins if required in Division 01.
- E. Warranties: Documentation indicated that existing warranties are still in effect after completion of selective demolition.

1.07 CLOSEOUT SUBMITTALS

- A. Inventory: Submit a list of items that have been removed and salvaged.
- B. Landfill Records: Indicate receipt and acceptance of hazardous wastes by a landfill facility licensed to accept hazardous wastes.

1.08 FIELD CONDITIONS

- A. Owner will occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted.
- B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.

- C. Notify Owner of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
- D. Hazardous Materials: Hazardous materials are present in buildings and structures to be selectively demolished. A report on the presence of hazardous materials is on file for review and use. Examine report to become aware of locations where hazardous materials are present.
- E. Storage or sale of removed items or materials on-site is not permitted.
- F. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.
 - 1. Maintain fire-protection facilities in service during selective demolition operations.
 - 2. Provide fire-watch for any facilities whose water system will be impacted.

1.09 WARRANTY

- A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials so as not to void existing warranties. Notify warrantor before proceeding.
- B. Notify warrantor on completion of selective demolition, and obtain documentation verifying that existing system has been inspected and warranty remains in effect. Submit documentation at Project closeout.

PART 2 - PRODUCTS

2.01 PERFORMANCE REQUIREMENTS

- A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- B. Standards: Comply with ANSI/ASSE A10.6.

PART 3 - EXECUTION

3.01 EXAMINATION

- A. Verify that utilities have been disconnected and capped before starting selective demolition operations.
- B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.
- C. Survey of Existing Conditions: Record existing conditions per Division 01.

- D. Perform an engineering survey of condition of building to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of structure or adjacent structures during selective building demolition operations.
 - 1. Perform surveys as the Work progresses to detect hazards resulting from selective demolition activities.
- E. Survey of Existing Conditions: Record existing conditions by use of measured drawings and preconstruction photographs.
 - 1. Inventory and record the condition of items to be removed and salvaged. Provide photographs of conditions that might be misconstrued as damage caused by salvage operations.
 - 2. Before selective demolition or removal of existing building elements that will be reproduced or duplicated in final Work, make permanent record of measurements, materials, and construction details required to make exact reproduction.

3.02 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage.
 - 1. Comply with requirements for existing services/systems interruptions specified in Division 01.
- B. Existing Services/Systems to Be Removed, Relocated, or Abandoned: Locate, identify, disconnect, and seal or cap off indicated utility services and mechanical/electrical systems serving areas to be selectively demolished.
 - 1. Owner will arrange to shut off indicated services/systems when requested by Contractor.
 - 2. Arrange to shut off indicated utilities with utility companies.
 - 3. If services/systems are required to be removed, relocated, or abandoned, provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
 - 4. Disconnect, demolish, and remove fire-suppression systems, plumbing, and HVAC systems, equipment, and components indicated to be removed.
 - a. Piping to Be Removed: Remove portion of piping indicated to be removed and cap or plug remaining piping with same or compatible piping material.
 - b. Piping to Be Abandoned in Place: Drain piping and cap or plug piping with same or compatible piping material.
 - c. Equipment to Be Removed: Disconnect and cap services and remove equipment.
 - d. Equipment to Be Removed and Reinstalled: Disconnect and cap services and remove, clean, and store equipment; when appropriate, reinstall, reconnect, and make equipment operational.
 - e. Equipment to Be Removed and Salvaged: Disconnect and cap services and remove equipment and deliver to Owner.
 - f. Ducts to Be Removed: Remove portion of ducts indicated to be removed and plug remaining ducts with same or compatible ductwork material.
 - g. Ducts to Be Abandoned in Place: Cap or plug ducts with same or compatible ductwork material.

3.03 PREPARATION

- A. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
 - 1. Comply with requirements for access and protection specified in Division 01.
- B. Temporary Facilities: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.
 - 1. Provide protection to ensure safe passage of people around selective demolition area.
- C. Temporary Shoring: Provide and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.

3.04 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
 - 1. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction.
 - 2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping, to minimize disturbance of adjacent surfaces. Temporarily cover openings to remain.
 - 3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
 - 4. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
 - 5. Maintain adequate ventilation when using cutting torches.
 - 6. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
 - 7. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
 - 8. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
 - 9. Dispose of demolished items and materials promptly. Comply with requirements of local governing agency require "Construction Waste Management and Disposal."

B. Removed and Salvaged Items:

1. Clean salvaged items.
2. Pack or crate items after cleaning. Identify contents of containers.
3. Store items in a secure area until delivery to Owner.
4. Transport items to Owner's storage area designated by Owner.
5. Protect items from damage during transport and storage.

C. Removed and Reinstalled Items:

1. Clean and repair items to functional condition adequate for intended reuse.
2. Pack or crate items after cleaning and repairing. Identify contents of containers.
3. Protect items from damage during transport and storage.
4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.

D. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Owner, items may be removed to a suitable, protected storage location during selective demolition and reinstalled in their original locations after selective demolition operations are complete.

3.05 SELECTIVE DEMOLITION PROCEDURES FOR SPECIFIC MATERIALS

A. Roofing: Remove no more existing roofing than what can be covered in one day by new roofing and so that building interior remains watertight and weathertight.

1. Remove existing roof membrane, flashings, copings, and roof accessories.
2. Remove existing roofing system down to substrate.

3.06 DISPOSAL OF DEMOLISHED MATERIALS

A. General: Except for items or materials indicated to be recycled, reused, salvaged, reinstalled, or otherwise indicated to remain Owner's property, remove demolished materials from Project site and legally dispose of them in an EPA-approved landfill.

1. Do not allow demolished materials to accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.

B. Burning: Do not burn demolished materials.

C. Disposal: Transport demolished materials off Owner's property and legally dispose of them.

END OF SECTION

SECTION 31 1000

SITE CLEARING

PART 1 - GENERAL

1.01 SECTION INCLUDES

- A. Removal of vegetation, grass, grass roots, shrubs, tree stumps, trees, upturned stumps, weed growth, tree roots, brush, masonry, concrete, rubbish, debris and other objectionable materials, within limits of construction.
- B. Removal of concrete and bituminous surfacing.
- C. Removal of existing fencing where indicated on Drawings.

1.02 RELATED SECTIONS

- A. Division 31 2200: Grading.
- B. Division 31 2326: Base Course.

1.03 REFERENCE STANDARDS

- A. Standard Specifications for Public Works Construction, current edition.

1.04 REGULATORY REQUIREMENTS

- A. Perform all work of this Section in strict accordance with applicable Government Codes and Regulations especially meeting all safety standards and requirements of CAL/OSHA, County of Los Angeles and the City of Pasadena. Provide additional measures, added materials and devices as may be needed as directed by the District Representative at no added cost to the District.
- B. Comply strictly to Rule 1404, South Coast Air Quality Management District.
- C. Coordinate clearing Work with utility companies.

PART 2 - PRODUCTS - NOT USED

PART 3 - EXECUTION

3.01 PREPARATION

- A. Verify that existing plant life designated to remain is tagged or identified.
- B. Identify a waste area for placing removed materials.

3.02 PROTECTION

- A. Protect existing structures and site improvements indicated to remain, from damage by approved methods and/or as authorized by the *District Representative*. Removal of all protections shall be when work of this Section is completed or when so authorized by the District Representative.
- B. Protect Existing Utilities indicated or made known to remain traversing the job-site and serving existing adjacent facilities.
- C. Protect Existing Trees and Shrubs indicated to remain by providing temporary surrounding fencing so located a sufficient distance away so that trees and shrubs will not be damaged by site-clearing operations.
 - 1. Protection Barrier: A protection barrier shall be installed around the shrubs or trees to be preserved. The barrier shall be constructed of a durable fencing material, such as plastic construction fencing, snow fence, or chain link. The barrier shall be placed at or beyond the drip line. "Drip line" as referred to herein means a line which may be drawn on the ground around the tree directly under its outermost branch tips and which identifies that location where rainwater tends to drip from the tree. Placement of barrier to be approved by District Representative (Grounds Supervisor). If barrier is placed inside the drip line, then 3/4 inch plywood must be placed over the root zone up to the drip line. The fencing shall be maintained in good repair throughout the duration of the project, and shall not be removed, relocated, or encroached upon without permission of the District Representative (Grounds Supervisor).
 - 2. Storage of Materials: There shall be NO storage of materials or supplies of any kind within the area of the protection barriers. Concrete, cement, asphalt materials, block, stone, sand and soil shall not be placed within the drip line of the tree(s).
 - 3. Fuel Storage: Fuel storage shall NOT be permitted within 150 feet of any tree to be preserved. Refueling, servicing and maintenance of equipment and machinery shall NOT be permitted within 150 feet of protected trees.
 - 4. Vehicles/equipment: NO parking or driving of vehicles or storage of equipment shall be permitted within the drip line of any tree to be preserved.
 - 5. Debris and Waste Materials: Debris and waste from construction or other activities shall NOT be permitted within protected areas. Wash down of Concrete, cement or asphalt handling equipment, in particular shall NOT be permitted within 150 feet of protected areas.
 - 6. Grade Changes: Grade changes can be particularly damaging to trees. Any grade changes should be approved by the District Representative (Grounds Supervisor) before construction begins and precautions taken to mitigate potential injuries.
 - 7. Damages: Any damages or injuries to the preserved trees (including pruning or cutting of such trees not in conformity with the International Society of Arboricultural Pruning Guidelines and ANSI A300 Pruning Standards) shall be reported immediately to the District Representative (Grounds Supervisor). Severed roots shall be pruned cleanly to healthy tissue, using proper pruning tools. Broken branches/limbs shall be pruned according to International Society of Arboricultural Pruning Guidelines and ANSI A300 Pruning Standards. In the event that any damage, injury, improper pruning or cutting of a protected tree is deemed to be so

substantial as to require its replacement (such determination to be made in the sole discretion of the District Representative), Contractor shall replace such tree with the same species and variety of tree, up to a box size of 48 inches, or if no such replacement is available, with a substitute species or variety as determined in the sole discretion of the District Representative. Any replacement tree shall be approved in advance by the District Representative. The value of the tree to be replaced shall be determined by a Certified Arborist selected by Contractor from the District's approved list of Registered Consulting Arborists. To the extent that the value of the replaced tree as determined by the Certified Arborist exceeds the cost of the replacement tree, Contractor shall be liable to District for such difference in value in addition to all costs associated with replacement of the damaged tree.

8. Removal of Existing Tree or Shrub: Prior to removing or cutting any trees designated for removal, the contractor shall coordinate with the District's Ground Supervisor. In the event that Contractor, a Subcontractor, Sub-Subcontractor, material supplier or anyone else performing the Work of the Contract willfully, negligently or mistakenly removes any tree or shrub not designated for removal, Contractor shall immediately report such removal to the District Representative (Grounds Supervisor). Contractor shall replace such tree with the same species and variety of tree, up to a box size of 48 inches, or if no such replacement is available, with a substitute species or variety as determined in the sole discretion of the District Representative. Any replacement tree shall be approved in advance by the District Representative. The value of the tree to be replaced shall be determined by a Certified Arborist selected by Contractor from the District's approved list of Registered Consulting Arborists. To the extent that the value of the replaced tree as determined by the Certified Arborist exceeds the cost of the replacement tree, Contractor shall be liable to District for such difference in value in addition to all costs associated with replacement of the damaged tree.
9. Unauthorized Tree Removal or Injury: Criminal Penalties: Reference is made to California Penal Code §384a which provides that any person who willfully or negligently cuts, destroys, mutilates or removes any tree or shrub or portion thereof growing on public land without a written permit from the owner of said public land is guilty of a misdemeanor, subject to a fine of up to \$1,000, imprisonment in county jail for up to 6 months, or both. Contractor is advised that, in addition to all remedies provided herein and in the Contract Documents, the District shall cooperate with appropriate authorities in prosecuting and enforcing Penal Code §384a and other criminal sanctions as appropriate concerning trees and shrubs located on District property.
10. Preventive Measures: Before construction begins fertilization of the affected areas to be applied at a rate to be determined by the District Representative (Grounds Supervisor).

- D. Protect bench marks, survey control points, and existing structures from damage or displacement.

- E. Protection of Persons and Property (existing structures and site improvements):
 - 1. Provide barricades, warning signs at open depressions and holes on adjacent property and public accesses.
 - 2. Provide operating warning lights during hours from dusk to dawn each day or as otherwise required.
 - 3. Protect existing remaining structures, utilities, sidewalks, pavements other facilities from damage as caused by settlement, undermining, washout or other hazards created by site- clearing operations of this Section.
- F. Use means necessary to prevent dust from becoming a nuisance to the public, to neighbors and to others performing work on or near the job-site.
- G. Maintain access to the job-site at all times.

3.03 CLEARING

- A. Clear areas required for access to site and execution of Work.
- B. Remove all rubbish and debris existing and resulting from work operations of this Section as soon as possible, do not allow to pile up. Do not burn rubbish and debris on the job-site.
- C. Where active utility lines need to be capped or plugged, perform such work in accordance with requirements of the Utility Company.

3.04 REMOVAL

- A. Remove debris, rock, and extracted plant life from site.
- B. Excavate and remove associated plumbing piping.
- C. Prior to demolition work, the Contractor shall notify the District Representative to identify the existing items for salvage purposes. The materials identified for salvage shall be returned to the District in a timely manner agreed upon by the District Representative.

3.05 REPAIRS

- A. During demolition and construction, ensure that trees, shrubs and other plant material and vegetation are protected inside and outside of the work zone and that the vegetation is being watered, maintaining the proper moisture content according to the season. Failed vegetation, including sod, due to lack of water, and/or plant material destroyed during construction period are to be replaced to equal or better size and condition at no additional cost to the District.
- B. If the irrigation system is damaged or modified during construction, it shall be repaired to the Districts standards, and shall be in equal or better condition than prior to damage or modification. All repairs shall be, inspected and approved by the District Representative (Grounds Supervisor) prior to backfilling or covering of said repairs. The District representative requires forty-eight hours prior notice, when contractor requests inspection of completed repairs. All repairs shall be made so as to ensure proper operation prior to the

close of the contract at no additional cost to the District.

- C. Controller Wires: If damaged, cut or removed, repair by splicing, soldering and silicone sealing. To ensure proper operation, reconnect the wires to the valve to correspond with the map on the controller to the correct station.
- D. Hydraulic Tubes: If damaged/cut or removed, repair by replacing the tubing using equal or better material.
- E. Valves: If damaged, repair/replace with equal or better material. All valves are to be flushed/cleaned thoroughly.
- F. Mainlines: If damaged, repair/replace with equal or better material. All lines are to be flushed/cleaned thoroughly.
- G. Lateral Lines: If damaged, repair/replace with equal or better material. All lines are to be flushed/cleaned thoroughly.
- H. Irrigation Heads: If damaged, repair/replace with equal or better material. All heads are to be flushed and filters cleaned thoroughly.
- I. Controllers: If damaged repair/replace with equal or better material.
- J. Backflow Prevention Devices: If damaged, repair/replace with equal or better material.
- K. Gate/Ball/Quick Coupler Valves: If damaged repair/replace with equal or better material.
- L. Valve Boxes: If damaged, repair/replace with equal or better material. Concrete boxes and concrete lids with the appropriate markings for identification shall be used. The top of the box shall be buried below finish grade, equal to existing depth or deeper. The top of the valve stems shall be 6" below the underside of the top of the box.
- M. Construction in grass areas: Sod shall be removed by sod cutting at a soil depth of 2", stored on site, and watered on a daily basis. Upon completion of work, stored sod shall be reinstalled over the areas disrupted due to construction. An option may be to bypass cutting the sod, however at the completion of the project, finish grading and installation of new Hybrid Bermuda GN -1 sod over the areas disrupted by construction shall be required.

3.06 EXCESS MATERIALS DISPOSAL

- A. Legally dispose of off-site materials removed and not to be reused. Adjacent areas shall be left clean.

END OF SECTION

SECTION 31 2316

EXCAVATION, BACKFILLING AND COMPACTING FOR PAVING

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes:

1. Excavating, backfill, and compacting for paved areas.
2. Installation of fill materials.

B. Related Requirements:

1. Division 01 - General Requirements.
2. Section 01 45 24 - Environmental Import/Export Materials Testing.
3. Section 31 1000 - Site Clearing.
4. Section 31 2200 - Grading.
6. Section 32 2326 - Base Course.
7. Section 32 0117 - Pavement Repair.
8. Section 32 1216 - Asphalt Paving.
9. Section 32 1313 - Concrete Paving

1.02 PROJECT REQUIREMENTS

A. Import and Export of Earth Materials:

1. Fees: Pay as required by authorities having jurisdiction over the area.
2. Bonds: Post as required by authorities having jurisdiction over the area.
3. Haul Routes and Restrictions: Comply with requirements of authorities having jurisdiction over the area.

1.03 QUALITY ASSURANCE

- A. Comply with Standard Specifications for Public Works Construction, current edition, except as modified herein.
- B. Sampling, testing, and certification of imported and/or exported soils shall be performed in accordance with Section 01 45 24 - Environmental Import/Export Materials Testing.

1.04 TESTING

- A. OWNER will retain a Geotechnical Engineer as an OWNER Consultant who will provide observations, tests, inspections and approvals identified in the Contract Documents as being responsibility of OWNER.
- B. Imported Soils: The Geotechnical Engineer will obtain initial product Sample for testing in accordance Article 3.05 of this Section.

1.05 PROJECT CONDITIONS

- A. Information on Drawings or in soils report does not constitute a guarantee of accuracy or uniformity of soil conditions over the Project site.

PART 2 - PRODUCTS

2.01 BASE MATERIALS

- A. Concrete Slabs on Grade: Provide "Crushed Aggregate Base "as specified in the Standard Specifications for Public Works Construction, Section 200: "Rock Materials," with ¾ inch maximum size aggregates. Provide 3-inch thick base, unless noted otherwise.
- B. Bituminous Surfacing: As indicated on Drawings and specified in Section 31 23 26 - Base Course.

2.02 FILL AND BACKFILL MATERIALS

- A. Fill and backfill materials shall be previously excavated materials or imported fill material, free of clods and stones larger than 3-inch, foreign materials, vegetable growths, sod, expansive soils, rubbish and debris. Material shall conform to these specified requirements and related sections.
- B. Fill material exhibiting a wide variation in consistency and moisture content shall be blended or aerated to stabilize and upgrade the material.
- C. Imported Fill Material:
 - 1. Provide suitable materials obtained from Project site excavations for earthwork and fill materials. If excavated materials are not of suitable quality or sufficient quantity, import additional materials as necessary.
 - 2. Imported fill shall be a granular material with sufficient binder to form a firm and stable unyielding subgrade and shall not have more than 60 percent of fines passing 200 mesh sieve. Material shall have a coefficient of expansion of not more than 2 percent from air dry to optimum moisture content and not more than 6 percent from air dry to saturation. Imported material shall be clean and free of rubbish, debris, and toxic or hazardous contaminants. Adobe or clay soils are not permitted.
- D. Brick rubble and broken concrete originating from the Project site shall be legally disposed of off the Project site. No such materials shall be imported from outside the Project site.
- E. Permeable Backfill:
 - 1. Provide permeable backfill material behind retaining structures consisting of gravel, crushed gravel, crushed rock, natural sands, manufactured sand, or combinations of these materials conforming to the following gradations:

Sieve Size:	Percentage Passing:
¾ inch (19mm)	100
⅜ inch (10mm)	80 to 100
No. 100	0 to 8
No. 200	0 to 3
 - 2. Those portions of fill material passing a No. 4 sieve shall provide a sand equivalent of at least 60.

3. Provided backing for weep holes shall consist of two cubic feet of aggregate in burlap sacks, securely tied. Aggregate shall conform to requirements for No. 3 concrete aggregate as specified in subsection 200-1.4 of the Standard Specifications for Public Works Construction.
4. Permeable Backfill Alternate Materials: Instead of the materials specified for retaining structures backfill, a drainage matting system, Miradrain by Mirafi, Inc., or equal, may be provided if reviewed and approved by the ARCHITECT.

PART 3 - EXECUTION

3.01 GENERAL

- A. Before initiating intrusive activities, contact Underground Service Alert of Southern California (USA or Dig Alert) to obtain a Dig Alert ticket for location information on buried public and USA member utilities and pipelines at least 48-hours prior to beginning work. A copy of the Dig Alert ticket shall be forwarded to the OWNER. For on-site utilities, retain a state-licensed third party underground utility locating service.
- B. Clear the Project site as indicated in Section 31 10 00 - Site Clearing.

3.02 PROTECTION

- A. Protect and guard excavations against danger to life, limb, and property as required by, but not limited to, Cal-OSHA regulations.
- B. Protect adjacent existing improvements including landscaping against damage.

3.03 EXISTING UTILITY LINES

- A. Protect existing utility lines from damage or displacement.
- B. Remove conduits or pipes not in service, exposed during Work, unless a minimum cover of 2 feet is provided. Remove concrete, clay or other non-metallic pipe over 8 inches in diameter, unless otherwise indicated.

3.04 EXCAVATION

- A. Unclassified Excavations: Comply with the Standard Specifications for Public Works Construction, Section 300: "Earthwork," except as modified herein.

3.05 FILL

- A. Unclassified Fill and Compaction: Comply with the Standard Specifications for Public Works Construction, Section 300: "Earthwork," except as modified herein.
- B. Provide fill materials as specified in Part 2 - Products. If excavated materials from the Project site are not of required quality or sufficient quantity, import additional materials as necessary.
- C. In addition to the requirements of this Section, import and/or exported materials shall comply with the requirements of Section 01 45 24 - Environmental Import/Export Materials Testing.
- C. Imported fill materials will be sampled by the Geotechnical Engineer for compliance with the requirements of Part 2 of this Section.
- D. The Geotechnical Engineer will submit samples to a DSA approved independent approved testing laboratory for testing.

- E. Initial sampling will be performed by the Geotechnical Engineer before importing material to the Project site. Identify the location of the source site in addition to the address, name of the person and/or entity responsible for the source site. The Geotechnical Engineer will obtain both the initial and additional samples from the identified site and will submit samples to the approved independent testing laboratory for testing.
- F. The Geotechnical Engineer will perform additional sampling during import operations. If the total quantity of import is determined to be greater than 1,000 cubic yards of material, one sample shall be obtained and submitted for testing for each 250 cubic yards of imported material. If the total quantity of import is determined to be less than 1,000 yards, one sample shall be obtained and submitted for testing for each 100 cubic yards of imported material.
- G. The independent approved testing laboratory will perform the required tests and report results of tests noting if the tested material passed or failed such tests and will furnish copies to the Project Inspector, ARCHITECT, OAR, DSA, CONTRACTOR, and others as required. Report shall state tests were conducted under the responsible charge of a licensed State of California professional engineer and the material was tested in accordance with applicable provisions of the Contract Documents, CBC, and the DSA. Upon completion of the Work of this Section, the independent testing laboratory and Geotechnical Engineer shall submit a verified report to the DSA as required by CBC.
- H. Bills of lading or equivalent documentation will be submitted to the Project Inspector on a daily basis.
- I. Upon completion of import operations, provide the OAR a certification statement attesting that imported material has been obtained from the identified source site.

3.06 INSTALLATION OF MATERIALS

- A. Fill or backfill materials shall be installed in horizontal layers of 6 inches, unless otherwise required. Each layer shall be evenly placed and moistened or aerated as necessary. Unless otherwise reviewed by the Geotechnical Engineer, each layer of fill material shall cover the length and width of the area to be filled before the next layer of material is installed. Top surface of each layer shall be installed to an approximate level with a crown or crossfall of at least 1 in 50, but no more than 1 in 20. Provide adequate drainage at all times during construction of the Work of this Section.

3.07 COMPACTING

- A. Each layer of fill material shall be compacted by tamping, sheepfoot rollers, or pneumatic-tired rollers to provide specified relative compaction. At inaccessible locations, provide specified compaction by manually held, operated and directed compaction equipment.
- B. Unless otherwise indicated, compact each layer of earth fill to a relative compaction of at least 95 percent.
- C. When fill materials, or a combination of fill materials, are encountered or provided which develop densely packed surfaces as a result of installation or compacting operations, scarify each compacted layer before installing the next succeeding layer.

3.08 INSPECTION AND TESTING

- A. The Geotechnical Engineer will inspect and test excavations, sample material quality as required in Part 2, and observe installation and compaction of fill materials.

- B. The Geotechnical Engineer will sample imported fill materials from their designated source before delivery to the Project site.
- C. Installation of backfill will be observed by the Geotechnical Engineer.
- D. The Geotechnical Engineer will inspect and test excavation Work before the installation of fill and/or other materials.
- E. Compaction: Test compaction in accordance with ASTM D1557, Method C.

3.09 PROTECTION

- A. Protect the Work of this Section until Substantial Completion.

3.10 CLEANING

- A. Remove rubbish, debris, and waste materials and legally dispose of off the Project site.

END OF SECTION

SECTION 31 2326

BASE COURSE

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes:

1. Installation of base material.

B. Related Requirements:

1. Division 01 - General Requirements.
2. Section 01 45 24 – Environmental Import / Export Material Testing.
2. Section 31 1000 - Site Clearing.
3. Section 31 2200 - Grading.
4. Section 31 2313 – Excavating, Backfilling and Compacting.
5. Section 31 2316 - Excavation and Fill for Paving.
6. Section 32 0117 – Asphalt Pavement Repair.
7. Section 32 1216 - Asphalt Paving.
8. Section 32 1313 – Concrete Paving.

1.02 SUBMITTALS

- A. Crushed aggregate base (CAB) shall consist of native rock without naturally occurring asbestos or recycled materials. The CONTRACTOR shall submit written documentation, which identifies the source, volume, and proposed transport date of the material for review and approval by OAR and PUSD prior to importing the material. A statement on company letterhead from the CAB source, stamped by either a California Professional Geologist or Engineer, which states that the subject materials are native rock, do not contain any recycled materials and that the source quarry does not mine ultramafic materials, a source of natural occurring asbestos shall be included in the submittal to OAR and PUSD. The CONTRACTOR may request variance from analytical testing required by Section 01 45 24 for CAB. To be considered for a variance, the CONTRACTOR shall submit a documentation package for OEHS approval, which includes all of the aforementioned information at least 48 hours in advance of planned import.

1. Frequently used suppliers include:

- a. Hansen Aggregates.
- b. Vulcan Materials, Reliance Company.
- c. Vulcan Materials Durbin.

- C. Product Data: Submit material source, technical information and test data for base materials. Gradation and quality certifications shall be dated within 30 days of the submittal.

- D. Sample: Submit sample of proposed base course material.

1.03 QUALITY ASSURANCE

- A. Comply with the following as a minimum requirement: Standard Specifications for Public Works Construction, current edition.

PART 2 - PRODUCTS

2.01 MATERIALS

- A. Crushed Aggregate Base (CAB) materials shall conform to the requirements of the Standard Specifications for Public Works Construction: Section 200 - Rock Materials.
- B. Crushed Miscellaneous Base (CMB) or materials generated on site shall not be used as a base course material.

2.02 MATERIAL APPROVAL

- A. Base material shall be inspected by the Project Inspector for gradation and material content prior to installation. The OWNER may choose to have additional tests performed by a geotechnical engineer, retained by the OWNER, before installation.

PART 3 - EXECUTION

3.01 INSTALLATION

- A. Install base course material in layers not exceeding 4 inches in thickness, unless required otherwise. Grade and compact to indicated levels or grades, cut and fill, water and roll until the surface is hard and true to line, grade and required section. Provide a relative compaction of at least 95 percent, unless otherwise required.
- B. Grade base course to elevations indicated on Drawings, ready to receive surfacing, in accordance with Section 31 22 00 - Grading.

3.02 PROTECTION

- A. Protect the Work of this section until Substantial Completion.

3.03 CLEANUP

- A. Remove rubbish, debris, and waste materials and legally dispose of off the Project site.

END OF SECTION

SECTION 32 0113

ROLLED SLURRY SEAL, EXISTING PAVEMENT

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes:

1. Asphalt emulsion slurry seal as indicated.

B. Related Requirements:

1. Division 01 - General Requirements.
2. Section 32 0117 - Pavement Repair.

1.02 SUBMITTALS

A. Shop Drawings: Submit plan indicating extent of areas to be sealed.

B. Product Data: Submit mix design.

1.03 QUALITY ASSURANCE

A. Comply with the following as a minimum requirement: Standard Specifications for Public Works Construction, current edition.

PART 2 - PRODUCTS

2.01 MATERIALS

A. Slurry Seal: Provide the following material grades in accordance with Section 203 - Bituminous Materials of the Standard Specification for Public Works Construction, current edition.

1. Emulsified asphalt shall be slow set type grade CSS-1h.
2. Grading of the combined aggregate and percentage of emulsified asphalt shall conform to Type I slurry requirements.
3. Installed slurry seal shall be sufficiently cured to permit vehicle traffic within one day after application.

PART 3 - EXECUTION

3.01 REPAIRING AND ROLLED SLURRY SEAL EXISTING SURFACES

A. Preparation of Surfaces:

1. Before starting slurry seal operations, existing bituminous surfacing shall be cleaned of loose material, oil spots, vegetation, and other objectionable material.
2. Dampen surface to receive slurry seal with a light application of water to ensure coverage and proper bond.

3. Provide adequate protection over manholes, yard boxes, utility vaults and other improvements adjacent to the areas to receive slurry seal. Project Inspector shall inspect surfaces before the installation of slurry seal.
- B. Repair of Existing Surfacing: Cracks more than ½ inch wide, low areas, holes or depressions in existing surfacing shall be repaired as specified in Section 32 0117: Asphalt Pavement Repair, prior to the installation of slurry seal.
- C. Rolled Slurry Seal: Work shall be performed in accordance to Sub-section 302-4, Slurry, of the Standard Specifications for Public Works Construction, current edition.
 1. Roll slurry surfacing with a 10-ton pneumatic roller with a tire pressure of 50 psi and equipped with a water spray system. Roll as soon as the surfacing is sufficiently cured and will not pick up on tires of roller. Surfaced areas shall receive a minimum of two coverage passes by roller. Provide a smooth surface free from ridges or surface variations.
 2. Depressions occurring in cracks after initial slurry seal installation shall be filled with sand slurry before rolling and seal coat installation.

3.02 CLEAN UP

- A. Remove rubbish, debris and waste materials and legally dispose of off the Project site.

3.03 PROTECTION

- A. Protect the Work of this section until Substantial Completion.

END OF SECTION

SECTION 32 0117
ASPHALT PAVEMENT REPAIR

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes:

1. Bituminous Surfacing Repair: Areas removed for utility trenches, heaved by tree roots, cracked areas, protruding areas where pavement meets hard surfaces, depressed areas, holes and areas around new structures, and raveled bituminous pavement.
2. Areas heaved by tree roots, cracked areas, holes and trenches, and areas around new structures.

B. Related Sections:

1. Division 01 - General Requirements.
2. Section 31 2200 - Grading.
3. Section 31 2313 - Excavation and Fill.
4. Section 31 2316 - Excavation and Fill for Paving.
5. Section 31 2326 - Base Course.
6. Section 32 0113 - Rolled Slurry Seal, Existing Pavement.
7. Section 32 1216 - Asphalt Paving.
8. Section 32 1313 - Site Concrete Work.

1.02 SUBMITTALS

- A. Shop Drawings: Submit Shop Drawings indicating areas to be repaired.
- B. Product Data: Submit manufacturer's technical data for materials and products.

1.03 QUALITY ASSURANCE

- A. Comply with Standard Specifications for Public Works Construction, current edition.

PART 2 - PRODUCTS

2.01 MATERIALS

- A. Base course materials: Section 31 2326 - Base Course.
- B. Asphalt paving materials: Section 32 1216 - Asphalt Paving.
- C. Seal materials: Section 32 1236 - Seal for Bituminous Surfacing.
- D. Headers: Section 32 1216 - Asphalt Paving.

2.02 BITUMINOUS MATERIALS

- A. Provide materials and products of the class, grade or type indicated, conforming to relevant provisions of Section 203 - Bituminous Materials of the latest Standard Specifications for Public Works Construction.

PART 3 - EXECUTION

3.01 PAVEMENT REMOVAL

- A. Remove bituminous and concrete pavement in accordance with applicable provisions of Section 300 - Earthwork of the Standard Specifications for Public Works Construction.
- B. Pavement Heaved By Roots: Remove pavement to limits of distortion and expose roots. Trim roots to provide at least 12-inch clearance to pavement. Coordinate with OWNER's Tree Trimming Department for recommendations and approval prior to trimming roots.
- C. Remove protruding bituminous surfaces flush with the surrounding grade using a suitable tool or equipment so that adjacent finishes are not blackened.
- D. Remove raveled and depressed bituminous pavement to limits indicated or required.
- E. Saw cut existing improvements, trim holes and trenches in bituminous and concrete pavement to permit mechanical hand tampers to compact the fill.
- F. Remove broken concrete by saw cutting. If the required cut line is within 30 inches of a score or joint line or edge, cut and remove to the score, joint line, or edge.

3.02 EXCAVATING, BACKFILLING AND COMPACTING

- A. Conform to requirements in Section 31 2313 - Excavation and Fill; Section 31 2316 - Excavation and Fill for Paving; Section 31 2319 - Excavation and Fill for Structures; or Section 31 2323 - Excavation and Fill for Utilities, as required.
- B. Where subgrade or base is deemed to be unstable or otherwise unsuitable, excavate such materials to firm earth, and replace with a required material. Install and compact fill materials in accordance with the requirements of Section 31 2316 Excavation and Fill for Paving.

3.03 HEADERS

- A. Install headers along edge of bituminous surfacing abutting turf, earth, or planting area, unless indicated otherwise.
- B. Install headers so the bottom surface has continuous bearing on solid grade. Where excavation for headers is undercut, thoroughly tamp soil under the header. Compact backfill on both sides of header to the density of the adjacent undisturbed grade.
- C. Fasten headers in place with redwood or Douglas fir stakes of length necessary to extend into solid earth a minimum of 12 inches. Stakes shall be of sound material, neatly pointed, driven vertically, and securely nailed to headers. Space stakes, not to exceed 4 feet on centers with top of stakes set one inch below top of header. Provide a minimum of two 12d galvanized common nails through each stake.
- D. Remove existing headers where new surfacing is installed adjacent to existing surfacing.
- E. Install temporary headers at transverse joints of paving where continuous paving operations are not maintained.

- F. Provide additional stakes and devices as required to fasten headers.

3.04 BASE COURSE

- A. Unless otherwise indicated, base course shall be crushed aggregate base, fine grade, 3 inches thick or equal to thickness of the existing base, whichever is greater.
- B. Fill grade and compact as specified in Section 31 2200 - Grading.

3.05 RESURFACING

- A. Utility Trenches: Remove loose dirt and backfill with cement-sand slurry allowing for surfacing one inch thicker than existing. Resurface flush with existing adjoining pavement installing the same type of materials and section provided in existing improvements.
- B. Other Areas: Other surface improvements damaged or removed shall be cut to a neat even line and excavated one inch below the bottom of the existing pavement. Resurface by following the original grades and installing the same type of materials provided in existing improvements.
- C. Where bituminous surfacing abuts concrete, masonry, walks or paving, tamp joint smooth, if necessary, as described above to obtain a uniformly even joint, true to line and grade. Tamp and smooth materials before asphalt cools.

3.06 REPAIRING AND RESEALING EXISTING SURFACES

- A. Preparation of Surfaces: Prior to filling cracks, clean existing bituminous surfacing of loose and foreign materials and coat with a film of asphalt emulsion.
- B. Repair of Existing Surfacing:
 - 1. Fill cracks 1/2 inch wide and less with RS-1 emulsion and washed plaster sand or other OEHS approved crack filler material. Cracks larger than 1/2 inch wide shall be filled with Type F/Sheet Mix Asphalt Concrete as specified. Cracks shall be filled to the level of adjacent surfacing.
 - 2. Where low areas, holes, or depressions occur in existing surfacing, refer to Section 32 1216; Asphalt Paving, Article 3.02. Use Type E/School Mix and feather edge joint flush to the level of adjacent surfacing.
- C. Testing: Flood test entire area in presence of the Project Inspector. Inspect area after waiting one hour. Entire area tested shall be free of standing water or puddles in excess of 0.01 foot. Practical field measurement: 0.01 foot = two quarters stacked.
- D. Surface Seal: After surface has been repaired and tested, install seal coat over entire area indicated. Surface seal shall be as specified in Section 32 1236 - Seal for Bituminous Surfacing.

3.07 CLEANING

- A. Remove all stains on the Project site and adjacent properties caused by or attributed to the Work of this section.
- B. Remove rubbish, debris, and waste materials and legally dispose of off the Project site.

3.08 PROTECTION

- A. Protect the Work of this section until Substantial Completion.

END OF SECTION

SECTION 32 1723
PAVEMENT MARKINGS

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes:

1. Parking stripes, markings and accessibility symbols.
3. Fire lane "No Parking."
4. Curb marking and red curbs.

B. Related Requirements:

1. Division 01 - General Requirements.
2. Section 32 1216 - Asphalt Paving
3. Section 32 1313 - Concrete Paving
4. Section 32 1819 – Solar Reflective Pavement Coating

1.02 SUBMITTALS

- A. Shop Drawings: Submit Shop Drawings, indicating location, extent, color and texture of markings.
- B. Material Samples: Submit color Samples.

1.03 PROJECT CONDITIONS

- A. Do not install markings when adverse weather conditions are forecasted.

PART 2 - PRODUCTS

2.01 MATERIALS

- A. Paint: Pavement-Marking Paint: Latex, waterborne emulsion, lead and chromate free, ready mixed, complying with FS TT-P-1952, Type II, with drying time of less than 45 minutes.
 1. Dunn Edwards: Vin-L-Stripe.
 2. Pervo Paint Company: Acrylic Traffic Paint.
 3. Sherwin Williams: Setfast Acrylic Traffic Paint.
 4. Vista Paint Corporation: Traffic Paint.
 5. As approved equal by Architect/Engineer.

PART 3 - EXECUTION

3.01 PAVEMENT MARKINGS

A. Application of Paint:

1. Prior to application of paint, allow the pavement to properly cure. Clean and prepare in accordance with paint manufacturer's written recommendations.

2. For existing pavement, remove all existing markings. Clean and prepare in accordance with paint manufacturer's written recommendations.
3. Provide mechanical equipment to apply paint in a uniform, straight or curved pattern, without gaps, holidays, runs, or other defects.
4. Do not permit traffic until paint has completely cured.
5. Apply two coats in thickness recommended by manufacturer.

B. Marking Width and Color: Unless indicated otherwise, marking width and color are as follows:

<u>Location</u>	<u>Width</u>	<u>Color</u>
Parking stall lines	4 inches	White
Traffic markings		
Striping:	4 inches	Yellow
General	4 inches	Yellow
Accessible Parking	4 inches	Blue
International Symbol of Accessibility (ISA)	2 inches	White on blue background
Letters and numbers:		As indicated

3.02 PROTECTION

- A. Protect the Work of this section until Substantial Completion.

3.03 CLEANUP

- A. Remove rubbish, debris, and waste materials and legally dispose of off the Project site.

END OF SECTION 32 1723

SECTION 32 1819
SOLAR REFLECTIVE PAVEMENT COATING

PART 1 – GENERAL

1.01 SUMMARY

- A. Section includes: Solar reflective coating system over non-stamped asphalt pavement. System shall consist of a two-component epoxy-modified acrylic or an acrylic pigmented coating.
- B. Related Requirements:
 - 1. Division 01 - General Requirements.
 - 2. Section 32 0117 – Asphalt Pavement Repair.
 - 3. Section 32 1216 – Asphalt Paving.
 - 4. Section 32 1313 – Concrete Paving.
 - 5. Section 32 1723 – Pavement Markings.

1.02 REFERENCES

- A. ASTM International (ASTM):
 - 1. ASTM C67 – Standard Test Methods for Sampling and Testing Brick and Structural Clay Tile.
 - 2. ASTM D471 – Standard Test Method for Rubber Property – Effect of Liquids.
 - 3. ASTM D522 - Standard Test Method for Mandrel Bend Test of Attached Organic Coatings.
 - 4. ASTM D756 – Practice for Determination of Weight and Shape Changes of Plastics Under Accelerated Service Conditions.
 - 5. ASTM D1653 - Standard Test Method for Water Vapor Transmission of Organic Coating Films.
 - 6. ASTM D2047 – Standard Test Method for Static Coefficient of Friction of Polish-Coated Flooring Surfaces as Measured by the James Machine.
 - 7. ASTM D2240 - Standard Test Method for Rubber Property – Durometer Hardness.
 - 8. ASTM D4060 – Standard Test Method for Abrasion Resistance of Organic Coatings by the Taber Abraser.
 - 9. ASTM D4541 - Standard Test Method for Pull-Off Strength of Coatings Using Portable Adhesion Testers.
 - 10. ASTM D5895 - Standard Test Methods for Evaluating Drying or Curing during Film Formation of Organic Coatings Using Mechanical Recorders.
 - 11. ASTM E303 – Standard Test Method for Measuring Surface Frictional Properties Using the British pendulum Tester.
 - 12. ASTM G151 – Standard Practice for Exposing Nonmetallic Materials in Accelerated Test Devices that Use laboratory Light Sources.

13. ASTM G155 – Standard Practice for Operating Xenon Arc Lamp Apparatus for Exposure of Materials.

1.03 DEFINITIONS

- A. Solar Reflective Pavement Coating: High reflective coating that reduces the amount of heat absorbed into the pavement, lowering the temperature of the pavement.

1.04 SUBMITTALS

- A. Shop Drawings: Submit layout plans drawn to scale for the coordination of playground equipment. Indicate playground equipment locations extent of coating and colors.
- B. Color Samples: Submit manufacturer's color charts indicating the full range of colors available.
- C. Product Data: Submit manufacturer's descriptive data and application instructions.
- D. Safety Data Sheets, approved by the OEHS.
- E. Maintenance Instructions: Submit maintenance and cleaning instructions.

1.05 QUALITY ASSURANCE

- A. Qualifications:
 1. Manufacturer: Continuously engaged in manufacturing coating of similar type to that specified, with a minimum of five years successful experience.
 2. Installer: Shall be approved by manufacturer.
- B. Manufacturer's product shall be approved for use by Owners Office of Environmental Health and Safety (OEHS).

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Deliver manufactured materials in original package with seals unbroken and bearing manufacturer's labels.
- B. Store manufactured materials in a clean, dry location, protected from the weather and deterioration, and complying with manufacturer's written instructions for minimum and maximum temperature requirements for storage.

1.07 PROJECT CONDITIONS

- A. Environmental Limitations: Do not install coating over wet or damp substrates.
- B. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit coating to be applied according to manufacturer's written instructions.

1.10 WARRANTY

- A. Provide a guarantee against defects in the materials and workmanship for a period of five years from the date of Substantial Completion.

PART 2 – PRODUCTS

2.01 MANUFACTURERS

- A. Two-component epoxy-modified acrylic coatings:

1. GAF:
 - a. Coating: StreetBond SB 120.
 2. Decocoat Polymer Systems DP 200.
 3. Equal.
- B. Acrylic pigmented coatings:
1. Life Deck Specialty Coatings:
 - a. Life Deck 28 Series.
 - b. Life Deck primer 25 Series Parts A and B.
 2. Equal.

2.02 MATERIALS

1. Properties:
 - a. Dry Time (To re-coat): 35 minutes, per ASTM D5895.
 - b. Taber Wear Abrasion Dry H-10 wheel: 0.03 g/1000 cycles, per ASTM D4060.
 - c. Taber Wear Abrasion Wet H-10 wheel: 0.68 g/1000 cycles, per ASTM D4060.
 - d. QUV Accelerate Weathering Environment: 0.76 (Brick), per ASTM G151.
 - e. Hydrophobicity Water Absorption: 10.272% per ASTM D471.
 - f. Shore hardness: 42.3, per ASTM D2240.
 - g. Mandrel Bend: 1/4" @ 21° C per ASTM D522.
 - h. Permeance: 13.43g/m²/ 24hr/mmHg (52 mils), per ASTM D1653.
 - i. Adhesion to Asphalt: > 300 psi (1980 psi), per ASTM D4541.
 - j. Friction: Wet=66 and Dry=88.3, per ASTM E303.
- A. Acrylic System:
1. Coating: 100% acrylic pigmented coating.
 2. Properties:
 - a. Anti-Slip, Passes ASTM D2047.
 - b. QUV Accelerated Weathering Environment, ASTM G155, 1000 hours, Pass. No cracking, spalling, softening, or other surface deteriorations occurred.
 - c. Freeze/Thaw, ASTM C67, 50 Cycles, Pass, no breakage.
 - d. ASTM D756, Pass. No cracking, spalling, softening, or other surface deteriorations occurred.
- B. Colors: Colors shall have a Solar Reflectance Index (SRI) no higher than 40.

PART 3 - EXECUTION

3.01 EXAMINATION

- A. Product shall be applied by a manufacturer accredited applicator.

- B. Verify that substrates are satisfactory for coating according to manufacturer's written requirements. Pavement surface shall be dry and free from foreign matter, including but not limited to dirt, dust, and chemical residue. Areas containing chemical contaminants such as vehicle fluids shall be treated using a degreasing solution.
- C. Remove pavement markings by water-blasting, grinding, or other mechanical methods recommended by coating manufacturer. Removal should cause no damage to the pavement surface.
- D. Proceed with application only after unsatisfactory conditions have been corrected and surface is clean and completely dry.

3.02 MASKING

- A. Use duct tape, painter's tape, masking tape or comparable tapes to mark the edges of the area to be sprayed.
- B. Mask off areas where coating or overspray is not wanted using plastic sheeting, tarps, coating shield, paper or other suitable products.

3.03 APPLICATION

- A. Apply coatings only when the air temperature is 50°F and rising and will not drop below 50°F within 24 hours. No precipitation should be expected within 24 hours.
- B. Mix following manufacturer's instructions using recommended equipment.
- C. Lay out game lines with chalk lines.
- D. Tape and mask areas with different colors. Allow 1/4 inch overlap for masking on base color to prevent exposed asphalt gaps.
- E. Apply three coats of colors as indicated on plans to minimum 19 mil dry thickness. Apply the final coat with an 18" (inch) X 3/4" (inch) nap synthetic roller to even out the surface coverage. Allow at least one-day drying time between coats for exterior work or as directed by Project Inspector for proper drying.
- F. Apply two coats of game lines, per Section 32 1723, Pavement Markings.
- G. Apply per manufacturer's instructions. Spray sealer throughout coated area.

3.04 CLEANING

- A. Remove debris, rubbish, and waste material and legally dispose of off Project site.
- B. Clean coating as recommended in writing by manufacturer.
- C. Prevent any type of traffic over system for at least 48 hours after installation. Protect surface system until Substantial Completion.

END OF SECTION